

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N. R. 29 W


Dickinson COUNTY

DESCRIPTION OF CORNER Section corner for Sections 16,17,20 and 21

CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/15/60

WITNESSES TO CORNER..... 8" Tamarack (S 21 NBT) S 33° E 28 ½ Links



6" Tamarack (S 17 NBT) N 50° W 44 ½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from stream to South and East. Old face on Cedar found facing corner. Two badly rotted spruce stump bottoms in proper distances and bearings.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 2/21/61