

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R. 29 W


Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Sections 20 and 21

CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/15/60

WITNESSES TO CORNER..... 6" W. Pine (1/4" NBT) S 34 Links



CIRCLE CORNER REGISTERED

5" Balsam (1/4" NBT) N 36° E 05 Links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from old down cedar post which was proper distance and bearing from W. Pine $30^{\circ} N 20^{\circ} W$ 53 Links which had old axe marks, but is badly burnt and rotted condition.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 2/21/61
REGISTERED LAND SURVEYOR
Billy D. Buckler