

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 44 <sup>N.</sup> / <sub>XX</sub> R. 29 <sup>E.</sup> / <sub>W.</sub>	A2
2. PROPERTY CONTROLL- ING IN SECTION _____	6, T. 44 <sup>N.</sup> / <sub>XX</sub> R. 29 <sup>E.</sup> / <sub>W.</sub>	10
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> / <sub>S.</sub> R. _____ <sup>E.</sup> / <sub>W.</sub>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 3, 1974, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner A2 - 1/4 corner between Sections 1 & 6, T44N, R29-30W:**  
 Spruce post (Not found. No subsequent monuments found.)  
 W. Pine 18 S64W 29 ( " " " " accessories " )  
 W. Pine 10 N15E 44 ( " " " " " " )

**Corner 10 - S 1/16 corner between Sections 1 & 6, T44N, R29-30W:**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner A2:** Re-established proportionately on line between Sec. Cor. 40.012 ch. S and 39.862 ch. N. Corner falls 1 ch. S of ridge top as per original notes.  
**Corner 10:** Established on line between Sec. Cor. 20.006 ch. S and 1/4 cor. 20.006 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner A2:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.  
 Red Pine 14 N34°E (mag.) 173.7 ft. "1/4S, NBT"  
 Red Pine 14 S77°E (mag.) 381.8 ft. "1/4S, NBT"  
**Corner 10:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.  
 Corner in large open area; no suitable witness objects available.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE November 24, 1975  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

