

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <u>3</u> , R. <u>29</u> E. <u>W.</u>	A4 & B3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A4 - 1/4 corner between Sections 7 & 12, T44N, R29-30W:

Maple Post	(Not found. No subsequent monuments found.)
W. Pine 18 S36W 44	(" " " " accessories ")
W. Pine 20 N60E 33	(" " " " " ")

Corner B3 - 1/4 corner between Sections 6 & 7, T44N, R29W:

Wood post	(Not found. No subsequent monuments found.)
W. Pine 24 S25W 23	(" " " " accessories ")
W. Pine 24 N66E 30	(Probably found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner A4: Re-established 11/20/72 on line between Sec. Cor. 40.170 ch. to N and to S.

Corner B3: Re-monumented 5/22/75 from stump of probable BT noted above, badly burned and no marks, but agrees with original field notes as to species and size and with distances to original section corners S89°54'E 39.948 ch. and West 39.870 ch., the record distances being, respectively, 40.00 ch. and 39.82 ch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A4: 1" I.D. x 36" iron pipe with 4" aluminum cap
W. Pine 21 N24°W (mag.) 104.3 ft. "1/4S, NBT"
W. Pine 22 S21°W (mag.) 136.1 ft. "1/4S, NBT"

Corner B3: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
Aspen 5 N35°E (mag.) 14.4 ft. "1/4S, NBT"
Aspen 5 S53°E (mag.) 27.5 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE November 24, 1975
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

