

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 44 ^{N.} XX R. 29 ^{XX} W.	H5
2. PROPERTY CONTROLL- 9 ING IN SECTION_____	T. 44 ^{N.} XX R. 29 ^{XX} W.	14
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H5 (1/4 corner between Sections 10 & 15, T44N, R29W):
 Cedar Post (Probably found. No subsequent monuments found.)
 Cedar 14 S30W 29 (Not found.) No subsequent accessories found.
 Cedar 14 N20E 16 (Found.) " " " "

Corner 14 (South 1/16 corner between Sections 9 & 10, T44N, R29W):
 Not established in original survey and by approximation only, subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H5: On 9/19/75, replaced point of probable original post with monument shown below. Post point was at record bearing and distance from BT indicated above, identified by fire-charred witness blazes with axe marks. No trace of other BT.
Corner 14: Established 9/30/75 on line between Sec. Cor. 20.00 ch. S and 1/4 cor. 20.000 ch. N. Found 2" squared picket N10⁰W 40.6 ft. for approximate corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Balm-of-Gilead 6 N12⁰W (mag.) 62.3 ft. "1/4S, NBT"
 Balm-of-Gilead 3 S86⁰E (mag.) 32.0 ft. "1/4S, NBT"
Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 W. Spruce 6 N 6⁰E (mag.) 14.9 ft. "1/16S, BT"
 W. Spruce 5 S74⁰E (mag.) 27.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE January 21, 1976
Carl R. Johnson CHIEF OF BUREAU

APPROVED AND SIGNED BY Arthur O. Enger DATE January 21, 1976
MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources
 SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

