

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. R. 29 E.	C6 & D7
2. PROPERTY CONTROLLING IN SECTION	20 T. 44 N. R. 29 E.	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner C6** (1/4 corner between Sections 17 & 18, T44N, R29W):
 Cedar Post (Point of post probably found.)
 Cedar 10 S14E 24 (Not found. No subsequent accessories found.)
 Cedar 16 N19W 31 (Found. " " " ")
- Corner D7** (1/4 corner between Sections 17 & 20, T44N, R29W):
 Cedar 5 corner tree. No witnesses. (Not found. No subsequent monuments found.)
- Corner 3** (North 1/16 corner between Sections 19 & 20, T44N, R29W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner C6:** On 9/26/75, placed new monument described below at site of 2 old cedar post points and a standing cedar post, all at record distance from BT noted above, now a stump with old axe marks visible. One of post points may be original. Position checks with Y. Pine 24 line tree N0°02'E 6.586 ch. (record: 6.55 chains)
- Corner D7:** Re-established 9/25/75 on line between Sec. Cor. S88°35'W 40.220 ch. and N88°35'E 40.221 ch.
- Corner 3:** Established 9/16/75 on line between 1/4 cor. 19.342 ch. S and Sec. Cor. 19.342 ch. N. Corner falls in S'ly track of rut woods road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner C6:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap
 Cedar 10 N42°E (mag.) 17.6 ft. "1/4S, NBT"
 Cedar 5 S46°E (mag.) 14.1 ft. "1/4S, NBT"
 Cedar 8 S77°W (mag.) 22.8 ft. "1/4S, NBT"
- Corner D7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 Cedar 6 N26°W (mag.) 22.0 ft. "1/4S, NBT"
 Cedar 5 S70°E (mag.) 42.6 ft. "1/4S, NBT"
- Corner 3:** 1" I.D. x 24" iron pipe with 3 1/2" aluminum cap
 Red Maple 6 S63°E (true bearing) 30.5 ft. "1/16S, BT"
 Red Maple 4 North (true bearing) 33.7 ft. "1/16S, BT"
 Variation 2°07' East at this corner.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE January 23, 1976

APPROVED AND SIGNED BY Arthur O. Enger DATE January 23, 1976
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

