

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. R. <u>29</u> ^{W.} E.	E2
2. PROPERTY CONTROLL- ING IN SECTION <u>5</u>	T. <u>44</u> ^{N.} S. R. <u>29</u> ^{W.} E.	14 & 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner E2 (1/4 corner between Sections 4 & 5, T44N, R29W):
Cedar 18 corner tree (Not found. No subsequent monuments found.)
No witnesses (No subsequent accessories found.)
- Corner 14 (South 1/16 corner between Sections 4 & 5, T44N, R29W):
Not established in original survey nor subsequently, apparently.
- Corner 16 (East 1/16 corner between Sections 5 & 8, T44N, R29W):
Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner E2: Re-established 8/25/75 proportionately on line between Sec. Cor. 40.113 ch. S and 40.343 ch. N. Many old rotted cedar stumps in vicinity, but could not identify any as being the original corner tree.
- Corner 14: Established 9/23/75 on line between Sec. Cor. 20.056 ch. S and 1/4 cor. 20.057 ch. N.
- Corner 16: Established 12/9/75 on line between Sec. Cor. 20.130 ch. E and 1/4 cor. 20.130 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner E2: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap
Cedar 9 S57°W (mag.) 10.8 ft. "1/4S, NBT"
Cedar 5 N 7°E (mag.) 21.3 ft. "1/4S, NBT"
- Corner 14: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Cedar 8 N28°E (mag.) 29.5 ft. "1/16S, BT"
Cedar 10 S55°W (mag.) 53.5 ft. "1/16S, BT"
- Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Jack Pine 16 N42°W (mag.) 41.4 ft. "1/16S, BT"
Jack Pine 12 N28°E (mag.) 22.5 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE January 20, 1976

Carl R. Johnson CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY Arthur O. Enger DATE January 20, 1976

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

