

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} 38 R. <u>29</u> ^{W.} 38	B7
2. PROPERTY CONTROLLING IN SECTION _____	18 T. <u>44</u> ^{N.} 38 R. <u>29</u> ^{W.} 38	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S., R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 25, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B7 (1/4 corner between Sections 18 & 19, T44N, R29W):
 Cedar Post (Not found. No subsequent monuments found.)
 Tamarack 20 S48W 40 (" " " " accessories ")
 Tamarack 20 N26E 18 (" " " " " ")

Corner 16: (East 1/16 corner between Sections 18 & 19, T44N, R29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B7: Re-established proportionately on line between Sec. Cor. 40.287 ch. E and Sec. Cor. 40.237 ch. W. Proportionately, this position falls agreeably with original field note calls to stream to W and stream and rock knob to E.

Corner 16: Established on line between Sec. Cor. 20.144 ch. E and 1/4 cor. 20.143 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B7: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Tamarack 2 N76°W (mag.) 27.9 ft. "1/4S, NBT"
 Tamarack 15 S44°W (mag.) 49.6 ft. "1/4S, NBT"
Corner 16: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 B. Spruce 8 N12°W (mag.) 37.3 ft. "1/16S, BT"
 B. Spruce 4 S82°E (mag.) 16.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE January 26

APPROVED AND SIGNED BY Arthur O. Enger DATE January 26, 1975

MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

