

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. <del>XX</del> R. <u>29</u> <del>W.</del>	B5
2. PROPERTY CONTROLLING IN SECTION <u>18</u>	, T. <u>44</u> N. <del>XX</del> R. <u>29</u> <del>W.</del>	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 25, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner B5 (1/4 corner between Sections 7 & 18, T44N, R29W):**  
 Spruce post (Not found. No subsequent monuments found.)  
 Tamarack 8 N10E 9 ( " " " " accessories " )  
 Spruce 6 N35W 7 ( " " " " " " )
- Corner 1 (West 1/16 corner between Sections 7 & 18, T44N, R29W):**

Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner B5:** Re-established proportionately on line between Sec. Cor. 40.249 ch. E and Sec. Cor. 39.997 ch. W.
- Corner 1:** Established proportionately on line between 1/4 cor. 20.124 ch. E and Sec. Cor. 19.873 ch. W. Found a 2" x 2" x 4' squared hardwood post N84°W 50.7 ft. for an approximate corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Corner B5:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.  
 Cedar 7 N61°W (mag.) 5.9 ft. "1/4S, NBT"  
 Cedar 14 S57°E (mag.) 17.9 ft. "1/4S, NBT"
- Corner 1:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.  
 Red Pine 22 N61°W (mag.) 26.4 ft. "1/16S, BT"  
 Red Pine 8 S89 1/2°E (mag.) 23.3 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

