

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} EX R. <u>29</u> ^{EX} W.	<u>C5</u>
2. PROPERTY CONTROLLING IN SECTION <u>18</u>	T. <u>44</u> ^{N.} EX R. <u>29</u> ^{EX} W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S., R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____	_____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C5 (Section Corner 7, 8, 17, & 18, T44N, R29W):
 Spruce post (Possibly found hole left by rotted post.)
 Spruce 10 S59E 15 (Not found. No subsequent accessories found.)
 Spruce 8 N60W 9 (Not found. No subsequent accessories found.)

Corner 2 (East 1/16 corner between Sections 7 & 18, T44N, R29W):

Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C5: Re-monumented 8/14/75 at site of a hole made by a post point long since completely rotted away. This place had been re-monumented successively at later dates by two other cedar posts, rotted off, but points still in good condition in the ground. The post point hole is probably the original corner position, as it lies NW'ly 4.1 ft. of a position proportioned between an original line tree 13.352 ch. S and an original Sec. Cor. 79.905 ch. N.
Corner 2: Established 8/25/75 on line between Sec. Cor. 20.124 ch. E and 1/4 cor. 20.125 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C5: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap and 1/2"x12" iron rod welded to below-ground end.
 B. Spruce 8 N52°W (mag.) 13.4 ft. "S7, NBT"
 B. Spruce 7 N58°E (mag.) 14.1 ft. "S8, NBT"
 B. Spruce 8 S17°W (mag.) 25.7 ft. "S18, NBT"
Corner 2: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Cedar 8 S52°E (mag.) 9.9 ft. "1/16S, BT"
 Cedar 8 S44°W (mag.) 4.3 ft. "1/16S, BT"
 Cedar 8 S84°W (mag.) 23.3 ft. "1/16S, BT"
 Squared & scribed a 5" cedar N42W 1.0 ft. (to center of tree).

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 26, 1976

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

