

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{N.} S. , R. <u>29</u> ^{XX} W.	<u>C7</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 13, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C7 (Section Corner 17, 18, 19, & 20, T44N, R29W):

Cedar Post	(Not found. No subsequent monuments found.)	
Cedar 14 N45E 7	(" " " " accessories ")	
Cedar 12 S45W 40	(" " " " " ")	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner re-established on N & S axis on line between an identified line tree stump 6.641 ch. S and an identified original 1/4 cor. 42.378 ch. N, and on E & W axis by E'ly extension of a line from an original sec. cor. 80.524 ch. W through 2 stream crossings and over a rock knob called for in the original field notes. It is the opinion of the undersigned that the last described line is the key to the latitude of the subject corner, on the reasonable assumption that its departure is determined by the first mentioned line. The position is not agreeable with either the record distance to the line tree S or to a stream crossing N, but there are indications of blunders in the original measurement of the line between Sections 19 & 20 and the south half of the line between Sections 17 & 18. If the corner were set proportionately on this line, the calls on the line between Sec. 18 & 19 could not possibly be met; and since that line was run after the subject corner had been established, these calls logically seem superior to those on the N & S line as indicators.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1" of the latitude of the subject corner.

1" I.D. x 36" iron pipe with 3 1/2" aluminum cap and 1/2" x 12" iron rod welded to below-ground end.

White Spruce 6 S27°W (mag.) 17.1 ft. "S19, NBT"
 Black Spruce 5 N18°W (mag.) 39.9 ft. "S18, NBT"
 Variation 0°12' East at this corner.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 20, 1976

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

