LAND CORNER RECORDATION CERTIFICATE Filing Regulrement of Act 74, Mich. P.A. 1970

For corners in			•
_	Bickinson (County)	Located In:	Corner Code ≠
1.	Public Land Survey	T44 k299	
		<u> </u>	
		TB	-
		T R	
2.	Property Controlling	S T A	
	in Section	S T R	
_	6 61 Maria		


Register of Deeds Stamp & File Number

- . Recorded Plat 4. Lot No. _

Property in Sec.

<u>January 19, 1994</u> , 19 _ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in times 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land ent or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; setablished, re-established, monumented, re-monumented, recovered, found as

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

(Mt) Quarter corner common to Section 2 T44M-M29W, and Section 34 T45M-M29W. Corner restored in 1956 by Billy D. Buchler, RLS, as follows: Replaced 1/4 corner from one W. Pine stump (probable) B.T. Distance checks east and west along township line. Placed 1° pipe with 4" brass cap. MATs: 7" Jack Pine \$03E 18.5 links, 5" Jack Pine M24W 12 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(N1) Recovered Buckler's monument, a 1' gipe with 4' dis. bress Mich. Deptartment of Conservation cap, at record bearing and distance from the 1956 MBTs, both dead and down. Left the monument in place and marked 4 new mitness trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(N1) Found 1' pipe with 4' bress cap. Blazed and scribed the following new

bearing trees:

Bearings magnetic.

7" Jack Pine 6200 6.4" *1/45 NBT* 5' Jack Pine MAN 10.1' '1/45 MAT'

12" Jack Pine MOSW 14.8' "1/45 MBT" 6' Jack Pine \$81E 12.4' '1/45 HBT'

at aleas, STEPHAN J SZYSZKOSKI LAND SURVEYOR