

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94

For corners in
Dickinson

	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 29W	J4
	T 44N R 29W	K5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

K5 Jul 16 1996
J4 Jul 23 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


(J4) Center of Section 11. Corner not established in the original survey. Found no subsequent record.
(K5) Corner common to Sections 11-12-13-14. Corner established in 1848 by John Burt: "Set sugar post corner of Sections 11,12,13,14. Sugar 12 S75E 25, Lynn 24 N40W 36". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J4) Found no evidence of prior monumentation. Established the corner at the intersection of straight lines connecting opposite quarter corners 2647.75' north, 2648.10' south, 2659.84' east, and 2659.84' west. At the position for the corner, I placed a 1" I.D.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
(K5) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between monumented corners 200.468 ch. south, 80.188 ch. north, 79.588 ch. east, and 80.600 ch. west. At the position for the corner, I placed a 1" I.D.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J4) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following bearing trees: 2" Maple S05N 70.6' "1/4S BT" 6" J. Pine S44W 98.7' "1/4S BT" 2" W. Spruce N61W 41.8' "1/4S BT" 11" Aspen N39E 17.3' "1/4S BT" Placed a 4" oak post adjacent. Bearings are magnetic.	(K5) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following bearing trees: 8" W. Spruce N72E 15.7' "S12 NBT" 9" Sugar S53E 28.8' "S13 NBT" 6" dbl. Sugar S54W 16.7' "S14 NBT" 7" Sugar N41W 24.7' "S11 NBT" Placed 3" squared sugar post adjacent. Bearings are magnetic. Placed location poster on 5" poplar at S. side of E-W trail N20W 160' distant.
---	--



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date Sept. 3, 1996

For the Michigan Department of Natural Resources - Forest Management Division