

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

|   |                                      |               |           |
|---|--------------------------------------|---------------|-----------|
| <u>Dickinson</u><br><small>(County)</small> | Located In:                          | Corner Code # |           |
| 1. Public Land Survey                       | T ___ R ___                          |               |           |
|   | T ___ R ___                          |               |           |
|   | T ___ R ___                          |               |           |
| 2. Property Controlling<br>in Section       | S ___ T ___ R ___                    |               |           |
|   | S <u>1</u> T <u>44N</u> R <u>29W</u> |               | <u>13</u> |
|   | S <u>1</u> T <u>44N</u> R <u>29W</u> |               | <u>8</u>  |
| 3. Miscellaneous<br>Property in Sec.        | S ___ T ___ R ___                    |               |           |
|   | S ___ T ___ R ___                    |               |           |

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

|  |    |             |
|--|----|-------------|
|  | 8  | Jul 28 2005 |
|  | 13 | Jul 26 2005 |

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (13-Sec. 1) Southeast 1/16 corner, Section 1. Not established in the original survey.
- (8-Sec. 1) West 1/16 corner, Section 1. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (13-Sec. 1) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (8-Sec. 1) Established the corner midway and on a straight line between Quarter corner 1325.00' West and Center of Section 1325.00' East.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |
|--|--|
| (13) Set 1" IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>12" R.Pine N60E 34.7' mrkd "1/16S BT"<br>10" R.Pine S07E 14.9' do<br>9" Oak N15W 8.2' do<br>7" Oak N03W 15.9' do<br>Set sq'd cedar post adjacent. Bearings<br>are magnetic. Distances are to nail<br>with tag. | (8) Set 1" IDx32" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in:<br>8" J.Pine S67E 63.7' mrkd "1/16S BT"<br>10" triple Spruce N11E 88.6' do<br>6" B.Spruce S71W 86.0' do<br>4" J.Pine N19W 78.1' do<br>Set sq'd cedar post adjacent. Bearings<br>are magnetic. Distances are to nail<br>with tag. |
|--|--|

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/29/05