

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T ~~43-44~~ NR 29 W

Dickinson

COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sec.'s 32-5

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 8" Jack Pine S 90° W 37 1/2 links

Marked "1/4 S HBT"

8" Jack Pine S 72° E 66 1/2 links

Marked "1/4 S HBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from two white pine B.T.s' bearing N 38° E 42 links (badly burned) and N 12° W 13 links, down and burned. Notch plain and description blaze plain.

Found 1/4 Corner while checking lines run by Forestry Division Survey Crew while making a re-survey of this township.

No evidence of use.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 5/6/57