

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44-45 N R. 29 W


Dickinson and Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2, 3, 34, and 35

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 4/21/59

WITNESSES TO CORNER..... 9" J. Pine (S 35 NBT) N 70° E 14 Links



10" J. Pine (S 2 NBT) S 10° E 62 Links

9" J. Pine (S 3 NBT) S 45° W 103 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reset to corrected position. Moved corner, as formerly set by myself, to corrected position. Corner was set by Single Proportionate Measure. Corrected corner set by Double Proportionate Measure, using corner 1 mile South; 1 1/2 miles North; 1 mile East and 1/2 mile West. Old corner defaced. Corner lies 1.71 chains North of Random line.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4/12/61
REGISTERED LAND SURVEYOR
Billy D. Buckler