

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~44-45~~ NR. 29. ~~W~~ ..

Dickinson and
Marquette ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 2, 3, ~~29~~, 35. ---

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 8" Jack Pine S 61° E 31½ links -----

8" Jack Pine S 36° W 63½ links -----

8" Jack Pine N 20° E 53½ links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by single proportionate measure East and West along Township line.

From good corners:

1 mile East
½ mile West

Squared and scribed 6" Aspen at Corner.

No evidence of original corner.

Note: Compass variation = 9° 30' W at this corner.

Corner placed and witnessed September 25, 1956.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 10/15/56