

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> <sup>N.</sup> <del>34</del> R. <u>29</u> <sup>W.</sup> <del>30</del>	B1
2. PROPERTY CONTROLLING IN SECTION	<u>6</u> , T. <u>44</u> <sup>N.</sup> <del>34</del> R. <u>29</u> <sup>W.</sup> <del>30</del>	3
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ <sup>N.</sup> _____ <del>_____</del> R. _____ <sup>E.</sup> _____ <del>_____</del> <sup>W.</sup> _____	
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner B1 - 1/4 corner between Sec. 6 & 31, T44-45N, R29W:**  
 Y. Pine post (Not found. Found monument described below.)  
 Maple 4 N34E 13 (" " No subsequent accessories found.)  
 W. Pine 18 N61W 46 (" " " " " " )

**Corner 3 - N 1/16 corner between Sec. 1 & 6, T44N, R29-30W:**  
 Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner B1:** Re-established 11/27/74 proportionately on line between Sec. Cor. 39.984 ch. E and Sec. Cor. 39.554 ch. W. This corner previously re-established by B. Buckler, but proportionately on line between corners one of which is unacceptable to the undersigned. Monument indicated in C, below, is Buckler's, moved to the new position.

**Corner 3:** Established 12/3/74 proportionately on line between 1/4 cor. 20.006 ch. S and Sec. Cor. 19.856 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner B1:** 1" I.D. x 48" iron pipe with 4" brass cap.  
 Aspen 5 S6°E (mag.) 72.3 ft. "1/4S, NBT"  
 ⊕ Chiselled in granite boulder N73°W (mag.) 31.82 ft.

**Corner 3:** Falls on the south face near SE corner of a boulder about 16 ft. long E & W by 12 ft. wide N & S, by about 6 ft. high near its East end. No suitable witness trees near. Corner is marked with a chiselled ⊕.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE November 21, 1975

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

