

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY


T 44N R 29W

DESCRIPTION OF CORNER 1/4 corner between Sections 28 and 29

CORNER MONUMENT 1" I.D. x 48" iron pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED August 22, 1969

WITNESSES TO CORNER..... Red Pine 20 S7°E 30 lks. "1/4S, NBT"



White Spruce 10 N43°W 8 lks. "1/4S, NBT"

(Same trees as Buckler used)

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument moved 2 links south and 11 links west of former position established by B. D. Buckler on September 15, 1960. (See Buckler's corner record dated 2/21/61). Buckler had re-established this corner midway on line between an original section corner 1/2 mile south and a section corner re-established by himself 1/2 mile north. On account of a second re-establishment of the latter corner, using additional measurement evidence not available to Buckler, it was felt that this corner should be moved to maintain the same relationship with its controlling section corners as given by Buckler and the original record. Found no evidence of original post or its accessories. Distances N and S to section corners are 39.961 chains.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Enger
REGISTERED LAND SURVEYOR

DATE

1/28/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68