

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T ~~44-45~~ NR ~~28-29W~~

Dickinson and Marquette COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to 1-6-31-36 Township Corner

DESCRIPTION OF CORNER MONUMENT 1/2" X 30" Iron Bar buried in Road

WITNESSES TO CORNER 11" Jackpine (S36 NBT) N63°W 101 Lks.

11" Jackpine (S1 NBT) S38°W 120 Lks.

8" Red Oak (S6 NBT) S30°E 68 Lks.

8" Red Pine (S31 NBT) N14°E 114 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established twp. cor. by double proportionate measure in all four directions. Found no evidence of original cor., but did find a wood stake 13 Lks. west and 34 Lks. north of this cor. Cor. lies in approximate center of Floodwood Road. Placed post with location poster 25 Lks. north of cor. Cor. placed and wit. 4/10/59.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 8/21/59
REGISTERED LAND SURVEYOR