

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~43-44~~ NR. 29 W. . .

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec. 's 4-5-32-33 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER	6" W. Birch	S 87° E	14 links
		"S 4 NBT"	
	7" Aspen	N 22° W	20½ links
		"S 32 NBT"	
	7" Red Oak	S 44° W	86 links
		"S 5 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one white pine B.T. bearing N 51° W 15 links. Stub burned and in poor condition.

Corner found by Forestry Division Survey Crew.

Corner placed and witnessed November 20, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 1/21/58
REGISTERED LAND SURVEYOR