

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~43-44~~ NR 29 W . . .

Dickinson

COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 3-34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" Balsam S 72° E 14 links

8" B. Spruce "1/4 S NBT" S 20° W 16 links

"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 corner by single proportionate measure along township line east and west. Found no evidence of original corner.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/20/57
REGISTERED LAND SURVEYOR