

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. <sup>44</sup> NR. 29 W.

Dickinson

COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 8 and 17  
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap  
WITNESSES TO CORNER Cedar 8" S 59 W 10 links, Marked 1/4 S NBT  
Cedar 11" N 66 E 29 links, marked 1/4 S NBT

Distapces measured from NBT notch to center of brass cap.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner was replaced from one original tamarack bearing tree, down, in good condition, scribe marks plain, and one original cedar bearing tree in poor condition. Stump in place with scar tissue in overgrowth. Wood post in place.

Corner found while cruising timber in this area.

Corner placed and witnessed on 24 July 1957 with Norman J. Karsten.

SURVEYORS SEAL

*Henry S. Peterson*  
SIGNED Henry S. Peterson DATE 7/26/57  
REGISTERED LAND SURVEYOR