


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY  
T 44N R 29W

DESCRIPTION OF CORNER Section Corner 26, 27, 34, and 35  
CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED August 1, 1969  
WITNESSES TO CORNER..... Red Pine 6 N33°E 47½ lks. "S26, NBT"



Red Pine 5 S56½°W 86½ lks. "S34, NBT"  
Red Pine 6 S4°E 43 lks. "S35, NBT"  
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by double proportionate measurement between known corners approx. 1 mile E, 2 miles W, 1 mile N, and 1 mile S. Found no identifiable evidence of original corner post or its accessories or of any replacement monument or accessories. Found recent E & W line blazes on a 4" aspen 5 links South of corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur P. Engler  
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68