


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY
T 44N R 29W

DESCRIPTION OF CORNER South 1/16 corner between Sections 26 and 27
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED August 22, 1969
WITNESSES TO CORNER..... Tamarack 10 N10°W 4½ lks. "1/16S, BT"



W. Spruce 5 S66°E 20 lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between Sec. Corner 19.985 chains south and 1/4 corner 19.985 chains north. No evidence that a corner had ever been established here previously.

Variation 0°00' at this corner.

SURVEYOR'S SEAL

SIGNED

Arthur C. Enger
REGISTERED LAND SURVEYOR

DATE

1/28/71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68