


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY
T 44N R 29W

DESCRIPTION OF CORNER Section Corner 20, 21, 28, and 29
CORNER MONUMENT 1" I.D. x 48" iron pipe with 4" brass cap
DATE MONUMENT PLACED AND WITNESSED August 13, 1969
WITNESSES TO CORNER..... B. Spruce 10 N3°W 31½ lks. "S20, MBT"



B. Spruce 6 N78°E 30 lks. "S21, MBT"
Tamarack 5 S90°E 21 lks. "S28, MBT"
AND (Buckler's MBT's obliterated)

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument moved 0.8 links south and 22 links west of former position established by B. D. Buckler on 9/15/60. (See Buckler's corner record dated 2/21/61.) Buckler had essentially re-established this corner by measurements in a north-south direction only, with approximate checks to swamp edges to east and west. The undersigned had occasion to measure an east-west line through this corner from original corners 1 mile West and 2 miles East, and found a true double proportion places the corner as described above. The swamp edge west of the corner is too indefinite to be satisfactory for use in proportioning. Distance West to a stream crossing checks closely with corner as re-established by undersigned.

Variation at this corner is 0°54'E.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

1/28/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68