


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY
T 44N R 29W

DESCRIPTION OF CORNER Section Corner 22, 23, 26, and 27
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED May 12, 1969
WITNESSES TO CORNER..... White Spruce 10 S4^oE 49 links "S26 NBT"



White Spruce 6 N50^oE 28 links "S23 NBT"
White Spruce 7 N63^oW 17 $\frac{1}{2}$ links "S22 NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument set from a probable original cedar BT to the southwest. Found a down and burned cedar corresponding in size to the recorded original, with an apparent partially grown-over face and definite overgrowth on a piece of bark. The location checks almost exactly with stream crossings to the north and west as recorded in the original field notes, and with swamp edges to north and west. Swamp edges to the east and south are indefinite and inconclusive. General area of corner was located from proportionate measurements to known corners in four directions from this one.

Variation at this corner is 0^o15'West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

2/26/70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68