

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
Sagola Township		
1. Public Land Survey	T <u>44N</u> R <u>30W</u>	<u>MC W of J07</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, Jeremy J. Pipp, in a field survey on 5/09/2012AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MC W of J07) Meander Corner common to Sections 14 and 23 on West side of Silver Lake. 1848: John Burt, DS. No post noted witnessed by: Tamarack 4 N85W 1.16 ch (76.56'); Tamarack 4 N5 1/2W 246 links (162.36'); 19?? DCRC plan set depicts 1/4 corner position as being monumented, no measurements to position, no monument description given; Found 1 1/4" water pipe approximately 2 1/2 feet above grade near calculated 1/4 position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC W of J07) Accepted found water pipe as marking a position for a calculated 1/4 position (position is 4.16' South and 4.05' East of calculated MPOL position between I07 & K07 [5290.94']). Corner position reestablished by single proportionate measurement between the Northwest corner and said monumented calculated North One-Quarter corner position of Section 23 [2649.56']. GLO distance from the Northwest corner to the MC position is 39.70 Chains (2620.2 feet); monumented position at 2629.69 feet East of Northwest corner; position is +/-200 Feet from the Waters Edge (location falls in dry lake bed). Position is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC W of J07) DNR monument
 1" pipe w/MDNR cap (on line) WEST 84.62'
 1" pipe w/cap (@ calc 1/4S) EAST 19.87'
 12" Tw. Tamarack N08W 78.54' (MC, NBT)
 All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic. A carsonite rail was set North 1.5 feet



Signed by Jeremy J. Pipp
 Surveyor's Michigan License No. 50447

Date July 18, 2012

For the Michigan Department of Natural Resources, Office of Land and Facilities