

SURVEY & REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 1997 DEC 10 AM 8:07

For corners in **SECTION**

Dickinson Located In: Corner Code #
 (County)
Sagola Twp.

1. Public Land Survey T 44N R 30W I-5 & G-7
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

REGISTER OF DEEDS
 DICKINSON COUNTY
 RON MOSENFELDER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Edward Kazianka, in a field survey on November 6, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-5 Corner common to Sections 10,11,14 & 15.
 Post set by J. Burt, D.S. in September 1848.
 Tamarack 16 S79W 41 lks.
 Dept. of Conservation pipe & cap set by Dean DeLaMater on 10-9-51.
 Spruce 8 S30W 16 lks. Spruce 8 N15W 18 lks.

G-7 Corner common to Sections 15,16,21 & 22.
 Post set by J. Burt, D.S. in September 1848.
 Tamarack 10 N66W 228 lks. Tamarack 8 S44E 228 lks.
 Dept. of Conservation pipe & cap set by H.S. Peterson on 7-16-56.
 Spruce 5 N64E 21½ lks. Tamarack 4 S 05E 9½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5 Found Dept. of Conservation pipe & cap.
 Tamarack NBT alive. Spruce NBT rotted-off at base.

G-7 Found Dept. of Conservation pipe & cap.
 Both NBT's blown-over and dead.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN P.A. 74 OF 1970 AT A MEETING HELD ON 12-9-97
ROP
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5 Dept. of Conservation pipe & cap.
 Cedar 5 N32W 16.32 feet. Dbl. Cedar 10 N74E 19.85 feet.
 Cedar 11 S67E 11.15 feet. Cedar 6 S69W 25.30 feet.
 Carsonite Marker N45W 3.0 feet.

G-7 Dept. of Conservation pipe & cap.
 Tamarack 6 S 05E 6.00 feet. Tamarack 5 S60E 17.95 feet.
 Tamarack 4 S64W 18.70 feet. Tamarack 5 N86E 12.65 feet.
 B. Spruce 5 N11W 18.60 feet.
 Carsonite Marker S45W 3.0 feet.

All bearings are magnetic.



Signed by Edward Kazianka Date Dec. 10, 1997
 Surveyor's Michigan License No. 14765