

SURVEY & REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 DEC 10 AM 8:07

For corners in

Dickinson SECTION Located In: Corner Code #
(County)

Sagola Twp.

1. Public Land Survey T 44N R 30W I-7
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTER OF DEEDS
 DICKINSON COUNTY
 RON MOULTON, CLERK

Register of Deeds Stamp & File Number

I, Edward Kazianka, in a field survey on November 6, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-7 Corner common to Sections 14, 15, 22 & 23.
 Post set by J. Burt, D.S. in Sept. 1848.
 Y. Birch 10 S16E 40 lks. Y. Birch 24 N21W 33 lks.

ACCEPTED BY THE DICKINSON COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT
 345 OF 1990 AT A MEETING HELD ON
12-9-97
ROR
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 No evidence of the Original Corner or Accessories found, thus set the Section Corner by double proportionate measurement.
 The section corners one mile north and south are in with a distance of 10,542.64 feet between them and the section corners one mile east and west are set with a distance of 10,589.46 feet between them. Set the Section Corner 5,271.32 feet north of the corner common to Sections 22, 23, 26 & 27 and 5,297.38 feet east of the corner common to Sections 15, 16, 21 & 22.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 Set 2 1/2" Dickinson County Remon. Corner
 Aspen 7 S15E 11.44 feet. Aspen 6 S80W 9.29 feet.
 " 10 N31W 44.28 " . Cherry 8 N09E 18.40 "
 Carsonite Marker North 3.0 feet.



Bearings are magnetic.

Signed by Edward Kazianka Date Dec. 10, 1997

Surveyor's Michigan License No. 14765