

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 44N R 30W

DESCRIPTION OF CORNER Section Corner 1, 2, 11, and 12

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 12, 1970

WITNESSES TO CORNER..... E'ly of twin W. Birch 14 N13^oW (mag.) 16.0 ft. "S2, NBT"



Red Oak 9 N83^oW (mag.) 71.4 ft. "S2, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed from two yellow pine stumps believed to be the original BT's, as they correspond to the described originals in species, relative and absolute size, distance, and bearing. Corner also falls on side of a hill as per original record, and checks well with section corners 1 mile to N, S, and E, and with a river crossing W, when modern distances are proportioned. Found a 1¹/₂" I.D. iron pipe with marked pipe cap N15^oW 29.6 ft. from corner, possibly set by traverse from another corner by the State Highway Department in the mid-1930's. Could find no definite information on it, but nothing on the ground tends to support it.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

April 18, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68