

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 44N R 30W

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 2

CORNER MONUMENT 1" I.D. x 36' iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 22, 1970

WITNESSES TO CORNER..... Red Pine 23 N15°E (mag.) 76.9 ft. "1/4S, NBT"



Red Pine 18 S61°E (mag.) 75.3 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between section corners 40.035 ch. S and 39.845 ch. N. (Both DNR monuments). Record distances are 40.00 ch. and 39.81 ch., respectively.

Variation 0°45' East.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

April 19, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68