

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY


T 44N R 30W

DESCRIPTION OF CORNER North 1/16 corner between Sections 13 and 14

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 22, 1970

WITNESSES TO CORNER..... Aspen 10 S77°E (mag.) 26.8 ft. "1/16S, BT"



Aspen 8 S68°W (mag.) 1.7 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously.  
Corner established on line between an original 1/4 corner 19.99 ch. S  
and a probable original section corner 19.99 ch. N.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

April 19, 1972

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68