

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 44N R 30W

DESCRIPTION OF CORNER 1/4 corner between Sections 12 and 13

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 22, 1970

WITNESSES TO CORNER..... W. Pine 22 S34°E (mag.) 15.2 ft. "1/4S, NBT"



Red Oak 10 N46°W (mag.) 19.2 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established proportionately on line between section corners
40.29 ch. E and 40.30 ch. W.

Variation 0°45'W. Note: stony ground made it necessary to place the
monument at an angle. The punch mark in center of aluminum cap was placed
over the true point.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

April 19, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68