

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 44N R 30W

DESCRIPTION OF CORNER 1/4 corner between Sections 11 and 14

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED September 23, 1970

WITNESSES TO CORNER..... W. Birch 8 S85°E (mag.) 5.0 ;ft. "1/4S, NBT"



W. Birch 6 S21½°W (mag.) 38.2 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established proportionately on line between section corners
39.923 ch. E and 39.912 ch. W. Corner lies in lowland margin of Floodwood
Lake.

Variation 0°00'.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE April 19, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68