

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 30 W.

Dickinson

----- COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 13 and 14
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER Jack pine 8" S 70 E 9 1/2 links, marked T44N R30W 1/4 S NBT
Jack pine 7" N 79 W 23 links, marked, T44N R30W 1/4 S NBT
distances measured from center of brass cap to notches

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Replaced corner from two original white pine bearing trees. One stump shows scar tissue. Other stump was cut very low to ground. No marks visible. Both stumps at field note bearing and distance from corner and very solid.

Corner had been previously perpetuated by unknown surveyor. Wood post and 3" iron pipe in place. Michigan State Highway Department B.M. copper tag on post.

Corner was found by Clarence Ryberg while surveying planting land in this township.

Corner was placed with J. Doyle Veice on 19 October 1956

SURVEYORS SEAL

Henry S. Peterson

Henry S. Peterson

SIGNED _____
REGISTERED LAND SURVEYOR

DATE 10/20/56