

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Dickinson

(County)

Located in:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling
 in Section

S 31 T 44 R 30W 1

3. Miscellaneous
 Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Mar 28 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20			22	23	24						
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 West 1/16 corner between Sections 30-31. Corner established in 1963 by Billy D. Buckler, RLS: "This corner was placed midway and on a line between Section Corner to West and 1/4 Corner to East. Placed 1" pipe with 4" aluminum cap. Witnesses to corner, 9" B. Cherry N68W 19 links, 6" W. Birch S20E 12.5 links". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Re-monumented the position established in 1963 by Buckler. Recovered both 1963 bearing trees, in good condition. Scribing is visible on the lower blaze of the Cherry, and the overgrown lower blaze of the Birch was chopped out to reveal the original marks. The 1963 monument was not recovered. Placed a new monument, a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, at record bearing and distance from the 1963 bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" MDNR cap.

The 1963 BTs:

10" triple B. Cherry N62W 12.5'

14" White Birch S17E 8.3'

Blazed and scribed the following new

bearing trees:

10" Maple N24W 8.9' "1/16S BT"

10" B. Cherry N66E 26.6' "1/16S BT"

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

4-8-96

Surveyor's Michigan License No.

33986