

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located in:

Corner Code #

1. Public Land Survey

T 44N R 30W

A7

T 44N R 30W

A3

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A3 Jul 01 1997

A7 Jun 25 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	15	14	13	12	11	10	9	8	7	6	5	4
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (A7) Corner common to Sections 13-24 T44N-R31W and Sections 18-19 T44N-R30W. Corner reestablished in 1969 by A.O. Enger, RLS: "Corner re-established on line between an original section corner 159.78 ch. S and a re-established section corner 79.89 ch. N. Corner is on a west facing slope of a high, narrow N & S ridge, just below the crest. Corner monument: 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: Red Maple 6 S401/2E 40 links, Red Maple 6 W771/2E 72 links".
 (A3) Corner common to Sections 1-12 T44N-R31W and Sections 6-7 T44N-R30W. Corner reestablished in 1968 by A.O. Enger, RLS: "Corner replaced from stumps of two white pines believed to be original 8T's...Corner monument: 1" iron pipe with 4" aluminum cap. Witnesses to corner: White Pine 12 S19E 23.5 links, White Pine 12 S39W 71.5 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A7) Recovered the 1969 monument as described, a 1" I.D. iron pipe capped with a 4" dia. cast aluminum MDNR tablet, in good condition, and at record bearing and distance from the remaining 1969 NBT, the Red Maple NE. The other maple NBT was apparently removed during construction of a N-S road, the centerline of which is about 12' east of the corner. My measurements to the corners noted above are 159.63 ch. South and 79.89 ch. North. I accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked 3 new witnesses as described below. There is a gate on the above mentioned road whose westerly gate post is 8' east and 3' south of the monument. Corner witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR.

(A3) Recovered the 1968 monument, as described, in good condition, and at record bearing and distance from the 1968 witnesses, both in good condition. Left the monument in place and marked three new accessories as described below. Corner witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate localizing the position of the corner:

(A7) Found 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 15" Spruce S23W 70.9'(slope) "S24 NBT"
 18" Spruce N51W 47.1'(slope) "S13 NBT"
 3" Ironwood N15E 19.4'(Horiz) "S18 NBT"
 The 1969 wit: Red Maple 9" in clump of 3, MOOE 72 links. Placed a squared sugar post adjacent. Bearings are magnetic.

(A3) Found 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 4" Maple N36W 24.4' "S1 NBT"
 8" Maple N81E 16.0' "S6 NBT"
 8" Squared cherry S6SE 1.2' to notch
 The 1968 wits: 24" W. Pine S13E 15.5',
 16" W. Pine S43W 47.2'. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski
 33986

Date

Sept. 8, 1997

Surveyor's Michigan License No.

For the Michigan Department of Natural Resources - Forest Management Division