

65.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located in:

Corner Code #

1. Public Land Survey

T 44N R 30N A6

T R

T R

T R

2. Property Controlling
in Section

S 19 T 44N R 30N 10

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

10 Jul 08 1997

A6 Jun 25 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 10 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(A6) Quarter corner common to Section 13 T44N-R31N and Section 18 T44N-R30N. Corner reestablished by single proportionate measurement in 1969 by A.O. Enger, RLS: "corner re-established on line between section corners 39.945 chains to north and to south...Corner monument 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: B.Spruce 8 N66E 25.5 links, W.Spruce 5 S19W 9.5 links".
(10-Sec. 19) South 1/16 corner between Section 24, T44N-R31N and Section 19 T44N-R30W. Corner established in 1969 by A.O. Enger, RLS on line between Section corner 19.972 ch. South and 1/4 Corner 19.972 ch. North. Corner monument: 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: Basswood 13 N60E 50 links, Sugar Maple 13 S72W 33.5 links". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A6) Found Enger's monument in good condition, as described, a 1" I.D. iron pipe capped with a 4" cast aluminum MDNR tablet, at record bearing and distance from the remains of the 1969 bearing trees. Both were recovered as rotting stumps. My measurements from the monument to adjacent section corners are 2633.42' N. and 2639.5' S. The monument was found 1.7' west of a straight line between these corners. I accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked 4 new witnesses as described below. Corner recovered and re-witnessed by D.Lampela and B.Wheeler, Baraga District Office, MDNR.

(10-Sec. 19) Recovered the 1969 monument, as described, with a 4" dia. cast aluminum Michigan Dept. of Natural Resources tablet, in good condition, and at record bearing and distance from the 1969 witnesses, both found in good condition with overgrown blazes. Left the monument in place and marked two new accessories as described below. Corner re-witnessed by D.Lampela and B. Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A6) Found 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

18" W. Pine N86E 78.9' 1/4S NBT

4" Spruce N74E 35.2' 1/4S NBT

20" W. Pine N20W 71.5' 1/4S NBT

5" Spruce S44W 21.7' 1/4S NBT

Bearings are magnetic

(10) Found 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

6" Sugar S14E 9.6' 1/16S BT

5" Sugar N48W 30.6' 1/16S BT

The 1969 witnesses:

22" Basswood N63E 32.9'

18" Sugar S75W 22.1'

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

9/8/97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division