

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

67.

For corners in

<u>Dickinson</u>	Located in:	Corner Code #
(County)		
1. Public Land Survey	T 44N R 30W	AB
	T _____	_____
	T _____	_____
	T _____	_____
2. Property Controlling in Section	S _____	_____
	S _____	_____
3. Miscellaneous Property in Sec.	S _____	_____
	S _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jun 25 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(AB) Quarter corner common to Section 24 T44N-R31W and Section 19 T44N-R30W. Corner reestablished in 1969 by A.O. Enger, RLS: "Corner re-established on line between re-established section corners 39.945 ch. to N and to S. Corner monument: 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: Sugar Maple 9 N8.5W 12.5 links, Elm 7 N49E 34 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(AB) Found the 1969 monument as described, a 1" iron pipe capped with a 4" cast aluminum MDNR tablet, in good condition, and at record bearing and distance from the 1969 witnesses. The Sugar is in good condition, the Elm is dead and down. My measurements to adjacent section corners are 2633.00' North and 2635.69' South. I accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked three new witnesses as described below. Corner witnessed by B. Wheeler and D. Lampela, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(AB) Found 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

16" Sugar S49N 47.1' 1/4S NBT"

8" Sugar N15E 16.3' 1/4S NBT"

10" Sugar S66E 29.3' 1/4S NBT"

The 1969 witness: Sugar Maple N09W 8.5'

Placed a squared post adjacent.

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

7/27/97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division