



4. An Act 132 survey recorded in Liber 1, Page 682 by Ron Helsel R.L.S. #18994 on August 19, 1973 identifies the corner as a found 3/4" iron pipe. Corner measured 2660.50' from L-9. Witnesses: "N 43° W, 88.21 ft., Nail and Cap East side Power Pole S 45° W, 79.80 ft., Nail and Cap North side 28" Maple, N 55° E, 91.04 ft., Nail and Cap South side 20" Maple."
5. An Act 132 survey recorded in Liber 2, Page 501 by Ronnie M. Lester R.L.S. #18998 on December 23, 1977 identifies corner as found 1/2" pipe measuring 2658.44' from L-9. Witnesses same as in A.4. above.
6. An Act 132 survey recorded in Liber 2, Page 958 by Ronnie M. Lester R.L.S. #18998 on June 26, 1979 has same measurement and witnesses as in A.5. above; monumentation not mentioned.
7. An Act 132 survey recorded in Liber 3, Page 297 by Ronnie M. Lester L.S. #18998 on April 17, 1981 has same measurement and witnesses as in A.5. above. Monumentation not mentioned.
8. An Act 132 survey recorded in Liber 3, Page 536 by Austin C. Williams R.L.S. #21275 on April 11, 1983 has same witnesses as in A.5. above. Monumentation and measurement not given.
9. An Act 132 survey recorded in Liber 4, Page 79 by Fred N. White R.L.S. #12034 on August 12, 1985 indicates he measured the corner 2658.37' from L-9. Monumentation and witnesses not given.
10. A L.C.R.C. recorded in Liber 3, Page 180 by Larry A. Bryan L.L.S. #25832 on January 17, 1992 identifies corner as a found 1/2" pipe with the same witnesses as in A.4. above.
11. An Act 132 survey recorded in Liber 8, Page 751 by Anthony Bumstead P.S. #41095 on September 1, 1999 identifies the corner as a found 1/2" pipe. Witnesses same as in A.4. above. Corner measured 2658.48' from L-9.

SURVEY &  
REMONUMENTATION

DEC 9 9 1999

SECTION