

**SURVEY &
REMONUMENTATION**

DEC 6 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in HAMLIN TOWNSHIP

EATON COUNTY

Located In:

Corner Code #

1. Public Land Survey	T <u>1</u> N	R <u>3</u> W	<u>M-11</u>
	T <u> </u>	R <u> </u>	<u> </u>
	T <u> </u>	R <u> </u>	<u> </u>
	T <u> </u>	R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u>	T <u> </u>	R <u> </u>
	S <u> </u>	T <u> </u>	R <u> </u>
3. Miscellaneous Property in Sec.	S <u> </u>	T <u> </u>	R <u> </u>
	S <u> </u>	T <u> </u>	R <u> </u>

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

Copy

99 NOV 12 AM 8:28

LIBER 4 PAGE 87

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on October 6, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original corner set by John Mullett D.S. in 1826 at a distance of 80.00 chains from M-13. "Set post cor. Secs. 25 & 36. W. Oak 18 S 16 1/2° W 1.65. Hickory 7 N 75° W 34."
- Notes in the margin of GLO records, author, date, nor monumentation given, show the following witnesses: "B.O. 24" S 42 1/2° E 128. B.O. 10 N 48 E 88." Distance South to A-11, Onondaga Twp., Ingham County: 27 links (17.82').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Did not find any modern survey monumentation near the intersection of the section line roads. Dug a 2' x 2' x 3' pit around a point 27 links (17.82') North of A-11, Onondaga Twp., Ingham County (1/2" iron and non-legible cap in Mon. Box). Found many brick fragments and large field stones near a medium-sized red sand stone. Red sand stone measured 17.96' to A-11, Onondaga Twp., and was ±1' West of centerline Waverly Road. Accepted position of red sand stone as the corner. Left red sand stone, refilled pit, and set a 3/4" x 24" iron form pin with a 2 1/2" diameter aluminum P.A. 345 cap #28414 over stone's position. Set a monument box around.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" x 24" iron form pin with a 2 1/2" diameter aluminum P.A. 345 cap #28414 in a monument box witnessed by:
Nail and Tag #28414 N. side 40" Oak S 55° E 36.05'
Nail and Tag #28414 W. side 22" Hickory S 35° E 70.60'
Nail and Tag #28414 E. side 24" Hickory S 20° W 117.24'
1/2" iron and non-legible cap in Mon. Box, A-11, Onondaga Twp., Ingham County, South 17.96'

Signed by Maurice H. Mahieu

Date 10-19-99

Surveyor's Michigan License No. 28414

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975

REVISED JAN, 1983
REVISED OCT, 1995

P.A. 345 EATON COUNTY
PEER APPROVED 10/12/99 *ru*



Maurice H. Mahieu