



3. Act 132 unrecorded survey by Ronnie Lester, P.S. #18998 on December 27, 1977 calls for corner as "Set ½" Bar & Cap" no witnesses given.
4. Doug Richardson, P.S. #31603 under the employment of Fred White Engineering Company performed a Boundary Survey which is unrecorded on December 12, 1991 which showed the corner and only referenced the Liber and Page of A-3.
5. Larry Bryan, P.S. #25832 recorded an Act 132 survey in Liber 6, Page 858 on April 28, 1997 and noted the following:  
Northeast corner Section 35, T1N, R3W, Liber 2, Page 481  
Found ½" bar & cap at intersection of extended fence lines East & West  
Found Nail & Tag Southwest side 4" Oak, NW 2.11'  
Found Nail & Tag Northwest side 10" Ash, ENE, 7.41'  
Found Nail & Tag North side 12" Ash, SE, 4.38'
6. Larry Bryan, P.S. #25832 performed an unrecorded Act 132 survey on June 10, 1997 and noted the monumentation and witness same as A-5.
7. Maurice H. Mahieu, P.S. #28414 recorded an Act 132 Survey in Liber 6, Page 794, on March 27, 1997 and noted the following:  
Found ½" Iron Rod, witnessed by:  
Nail & Tag #28414 South Side 10" Ash, N55°E 7.10'  
Nail & Tag #28414 West Side 12" Ash, S45°E 4.15'  
Nail & Tag #28414 North Side 10" Oak, N80°E 14.02'  
Nail & Tag #28414 SE Side 15" Oak, N15°E 32.72'
8. Karol Cerovec (Grove) P.S. #39075 under the employment of Accolade Surveying, Inc. recorded an Act 132 survey in Liber 7, Page 201 on October 24, 1997 and noted the following:  
Northeast Corner of Section 35 / Southeast Corner of Section 26  
Found ½" Bar & Cap  
Centerline of 12" Ash S85°E, 4.40'  
Centerline of 10" Ash N25°E, 7.30'  
Centerline of 14" Ash N45°W, 23.00'  
Centerline of 20" Maple in Old Barbed Wire Fence Line S30°E, 32.00'  
Centerline of 40" Triple Maple, N60°E, 30.5'  
Centerline of Utility Pole, East, 300'

SURVEY &  
MONUMENTATION

JAN 11 2001

SECTION