

SURVEY & REMONUMENTATION

APR 27 1995

FILED
Copy

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV -3 AM 11: 22

For corners in
EATON COUNTY
(County)

Located In: Corner Code #

BROOKFIELD TOWNSHIP

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>1N</u> R <u>4W</u> | <u>A-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PG 480

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

DAVID R. LOHR in a field survey on OCTOBER 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-6: 1. CORNER WAS NOT SET DURING ORIGINAL SURVEY OF 1825.
2. FOUND NO RECORD OF SUBSEQUENT SURVEYS IN COUNTY SURVEYORS RECORDS.
3. PRIVATE SURVEYOR'S RECORDS REVEAL NO ADDITIONAL DATA

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6: AS CORNER WAS NOT SET DURING ORIGINAL SURVEY AND NO SUBSEQUENT RECORD EXISTS IN COUNTY SURVEYOR'S RECORDS, EXCAVATION APPEARS FUTILE AT THIS LOCATION. HOWEVER, EXCAVATED 1' X 4' TRENCH ALONG LINE BETWEEN A-5 AND A-7. EXCAVATED NORTH END OF TRENCH ON EXTENSION OF FENCE LINE TO EAST, AND SOUTH END TO INCLUDE MIDPOINT LOCATION. EXCAVATED THRU 6" OF BIT. AND DOWN TO CLAY AT DEPTH OF 22". FOUND NOTHING. SET 3/4" X 24" STANDARD REMON BAR IN MONUMENT BOX, BY SINGLE PROPORTIONATE MEASURE, ON STANDARD TOWNSHIP LINE.

DISTANCE NORTH 2640.62', DISTANCE SOUTH 2640.62'
DISTANCE EAST 2627.05'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6: SET STANDARD 3/4" X 24" REMON BAR WITH PA 345 CAP #30090 IN MON. BOX 1' WEST CENTERLINE OF COCHRAN ROAD AND 2' SOUTH OF FENCELINE TO EAST. WITNESSED BY:

SET N/T 30090 S/S P. POLE	Az. 89°	39.13'
NW/CORNER OF HOUSE #6505	Az. 123°	132.56'
SET N/T 30090 W/S 14" BL. WAL.	Az. 172°	135.10'
SET N/T 30090 E/S 46" CATALPA	Az. 230°	40.10'
SET N/T 30090 NE/S POST	Az. 325°	59.53'



Signed by David R. Lohr

Date OCTOBER 25, 1994

Surveyor's Michigan License No. 30090

P.A. 345 EATON COUNTY

PEER APPROVED 10/26/94

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983