

NOV 02 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 93 OCT 27 PM 2:38
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>EATON</u> (County)	Located In:	Corner Code #
BROOKFIELD TOWNSHIP		
1. Public Land Survey	T <u>1N</u> R <u>4W</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PAGE 326

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DAVID R. LOHR, in a field survey on OCTOBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-7 1. POST SET BY SYLVESTER SIBLEY, DEPUTY SURVEYOR IN 1825
WITNESSED BY: BEECH 8" NORTH 51 EAST 21 LINKS, BEECH 16" SOUTH 61 EAST 40 LINKS, AND (POST M-7 WALTON TOWNSHIP) NORTH 58 LINKS. (38.28')
- 2. NO RECORD OF SUBSEQUENT SURVEYS FOUND IN COUNTY SURVEYORS RECORDS.
- 3. PRIVATE SURVEYORS RECORDS REVEAL NO ADDITIONAL DATA.
- 4. EATON CO. ROAD COMM. PLANS (1917) SHOW CORNER TO BE 58 LKS. SOUTH OF M-7 AND 5' NORTH OF C/L MAHAN ROAD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7
NO PHYCIAL EVIDENCE EXISTS AS TO LOCATION OF A-7. SET CORNER AT RECORDED DISTANCE OF 58 LINKS (38.28') SOUTH OF M-7 WALTON TOWNSHIP, AND ON LINE BETWEEN M-7 AND M-8 WALTON TOWNSHIP. EXCAVATED THRU 6" OF BIT. CONCRETE AND 30" OF GRAVEL TO ORIGINAL GROUND (CLAY). FOUND NO EVIDENCE OF ORIGINAL CORNER. NO TOPSOIL WAS ENCOUNTERED DURING THIS EXCAVATION. IT IS PRESUMED THAT ANY EVIDENCE WAS REMOVED DURING PREVIOUS ROAD CONSTRUCTION.

SET STANDARD 3/4" X 24" BAR IN MONUMENT BOX ON CENTERLINE OF COCHRAN ROAD AND FIVE FEET NORTH C/L MAHAN ROAD.

C. Description of monument for corner and accessories established to perpetuale locating the position of the corner:

- A-7
SET STANDARD 3/4" X 24" EATON COUNTY REMONUMENTATION BAR AND PA 345 CAP #30090
- FOUND NAIL AND TAG #11370, S/S POWER POLE, Az. 53 53.40'
- SET GALV. NAIL AND TAG #30090, SE/S 24" OAK Az. 215 42.22'
- SET GALV. NAIL AND TAG #30090, SW/S 18" OAK Az. 300 26.60'
- SET GALV. NAIL AND TAG #30090, SW/S FENCE POST Az. 322 49.45'
- 3/4" PIPE IN MON BOX (M-7 WALTON) Az. 0 38.28'



Signed by David R. Lohr

Date OCTOBER 13, 1993

Surveyor's Michigan License No. 30090

11-5-93

24
25