

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

For corners in

EATON COUNTY

(County)

BROOKFIELD TOWNSHIP

1. Public Land Survey

Located In:

Corner Code #

T 1N R 4W

A-8

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

FILED
Copy

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

NOV -3 AM 11:22

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

LIBER 3 PG 481

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID R. LOHR, in a field survey on OCTOBER 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- A-8: 1. CORNER NOT SET DURING ORIGINAL SURVEY OF 1825.
2. FOUND NO RECORD OF SUBSEQUENT SURVEYS IN COUNTY SURVEYORS RECORDS.
3. PRIVATE SURVEYOR'S RECORDS REVEAL NO ADDITIONAL DATA

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8: AS CORNER WAS NOT SET DURING ORIGINAL SURVEYS AND NO SUBSEQUENT RECORD EXISTS IN COUNTY SURVEYOR'S RECORDS, EXCAVATION APPEARS FUTILE AT THIS LOCATION, HOWEVER, EXCAVATED 12" X 24" HOLE THRU 7" BIT TO CLAY AT DEPTH OF 17" AT MIDPOINT LOCATION. FOUND NOTHING. SET STANDARD 3/4" X 24" REMON BAR. BY SINGLE PROPORTIONATE MEASURE AT MIDPOINT BETWEEN A-7 AND A-9, AND ON STANDARD TOWNSHIP LINE. POINT FALLS 44.32' SOUTH OF M-8, WALTON TOWNSHIP. THERE IS NO ADJACENT FENCELINE TO MARK ANY OCCUPATION LINE TO EAST.
DISTANCE NORTH 2653.12, DISTANCE SOUTH 2652.90'
DISTANCE EAST 2636.83

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8: SET STANDARD 3/4" X 24" REMON BAR/PA 345 CAP H30090 IN MON BOX 3' WEST OF CENTERLINE OF COCHRAN ROAD. WITNESSED BY:
SET N&T 30090 W/S P. POLE AZ 21° 316.43'
SET N&T 30090 N/S P. POLE AZ 108° 130.01'
SET N&T 30090 NE/S 6"ELH AZ 338° 112.00'
M-8 WALTON PIPE IN MON. BOX. AZ. 00° 44.32'



Signed by David R. Lohr

Date OCTOBER 25, 1994

Surveyor's Michigan License No. 30090

P.A. 345 EATON COUNTY
PEER APPROVED 10/26/94 RL