

**SURVEY &
REMONUMENTATION**

OCT 16 1993

LIBER 3 PAGE 261

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED
copy

93 OCT -7 AM 9:09

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

Register of Deeds Stamp & File Number

For corners in _____

Eaton Located In: _____ Corner Code =# _____
(County)

Brookfield Township

1. Public Land Survey T 1N R 4W _____ A-9 _____
T _____ R _____ _____
T _____ R _____ _____
T _____ R _____ _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | | |
| 13 | | | | | | | | | | | | |

I, David R. Lohr, in a field survey on May 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-9: 1. Post set by Sylvester Sibley, Deputy Surveyor, in 1825. Witnesses by: Bl. Ash 11" S26°E, 13 Lks., Bl. Ash 12" N34°E, 20 Lks.
- 2. Marginal Note in Road Commission copy of GLO notes, Page 163. Corner found by unknown surveyor on April 13, 1931. "Fd. stone and crockery about 8" deep. Witnessed by Oak 8" NW 54.0', Hickory 15" SE 58.5', Elm 24" SW, 43.5', 24" Oak SE 94.9'

- OVER -

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9: Found 1/2" iron with cap #11370 in Mon. Box as per Liber 2, Pg. 309. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9: Left 1/2" iron with cap #11370 in Mon. Box. Witnessed by;
 - Set N&T #30090 42" Oak w/s Az. 151° 74.46'
 - Set N&T #30090 24" Oak w/s Az. 106° 118.12'
 - Set N&T #30090 24" Hick. w/s Az. 142° 71.87'
 - Set N&T #30090 Tel. Pole s/s Az. 75° 138.72'
 - NW cor. house Az. 136° 93.10'
 - M-9 Walton iron in mon. box Az. 0° 54.65'

Signed by David R. Lohr
Surveyor's Michigan License No. 30090

Date August 6, 1993



P.A. 345 EATON COUNTY
PEER APPROVED 8/25/93 m

10/18/93

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JANUARY 1988

A. Continued

A-9: Eaton Co. Road Comm. field notes (Topographic Survey) dated 1-14-22, show corner found to be stone with crockery, witnessed by: 6" Oak, NE, 67.6'

15" Hickory, NW 77.3'

12" Ash, NE 63.2'

24" Oak, SE 94.9'

4. Marginal Note in Road Commission copy of GLO notes, Page 163. Corner found by unknown surveyor on July 1946, found stone and crockery, auto axle.

Witnessed by 15" Hickory 98.0' N18°W, 24" Oak 62.70' N68°W, 18" Maple, 59.3' S32°W; 30" Oak 93.2' S30°E.

5. Corner recorded by Richard Steadman ^{PS #11370} on Sept. 2, 1975, in Liber 2, Page 309. Found a stone with broken brick around it and an auto axle at the East side in the intersection of Cochran Rd. and Bellevue Highway in a hole 30" deep. Stone's location raised to surface with a 1/2" iron pipe with cap #11370 and set a monument box over it.

| | | | | |
|---------------|---------------|-------|---------|-------------------------------|
| Witnessed by; | 42" Oak | S25°E | 94.46' | (Fd. tree) |
| | 24" Oak | S72°E | 118.02' | (Fd. 28" Maple-meas. 118.12') |
| | 24" Hick. | S35°E | 71.95' | (Fd. tree) |
| | NW cor. house | S41°E | 93.10' | (witness OK) |

6. CORNER REFERENCED IN SURVEY BY RICHARD STEADMAN, P.S.#11370, DATED 9/10/75, RECORDED IN LIBER 1 OF SURVEYS, PAGE 967. " FOUND STONE AND RAISED WITH 1/2" PIPE IN MONUMENT BOX." WITNESSED BY T. POLE N38°E 72.38'
24" MAPLE S72°E 118.05'
24" HICKORY S35°E, 71.95'
7. CORNER REFERENCED IN SURVEY ROBERT REED, P.S.#19004, DATED 5/17/84 AND RECORDED IN LIBER 3 OF SURVEYS, PAGE 653. "1/2" IRON IN MONUMENT BOX". SAME WITNESSES AS ITEM #6 ABOVE.
8. CORNER REFERENCED IN UNRECORDED SURVEY #860-L, BY DOUG RICHARDSON, P.S. #31603, DATED 8/16/88. NO WITNESSES SHOWN. SURVEY SHOWS DISTANCE OF 2644.77' TO B-9.
9. PRIVATE SURVEYORS RECORD'S REVEAL NO ADDITIONAL DATA.