

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 3 PAGE 266

For corners in

<u>EATON</u> (County)	Located In:	Corner Code #
<u>BROOKFIELD TOWNSHIP</u>	† <u>IN</u> R <u>4W</u>	<u>B-9</u>
1. Public Land Survey	† _____ R _____	_____
	† _____ R _____	_____
	† _____ R _____	_____
	† _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED  
 Copy  
 93 OCT -7 AM 9:10

Register of Deeds Stamp & File Number  
 LINDA M. TWITCHELL  
 REGISTER OF DEEDS  
 EATON COUNTY, MICH.

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5											
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9	⊙												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DAVID R. LOHR, in a field survey on MAY 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 B-9

- POST SET BY SYLVESTER SIBLEY IN 1825. WITNESSED BY TAMARACK 8" NORTH 74° WEST, 07 LINKS; 10" TAMARACK, SOUTH 9° EAST, 17 LINKS.
- IN MARGINAL NOTE IN ROAD COMMISSION COPY OF GLO NOTES, PAGE 163, CORNER FOUND BY UNKNOWN SURVEYOR ON MAY 4, 1922. "FOUND AN IRON PIPE WITH A STONE ABOVE!" WITNESSED BY: OAK POST, NORTH 20.4'. POST IN LINE WITH FENCE; EL; POST SOUTH 28.3'; 12" POPLAR SOUTH 38.8'

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 B-9

FOUND 5/8" X 18" REBAR IN MONUMENT BOX.  
 THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ADDENDUM: HAND EXCAVATED INTERIOR OF MONUMENT BOX. FOUND TOPSOIL AT DEPTH OF 18"; DUG TO 32" DEEP. FOUND NOTHING ELSE. DISTANCES ON SURVEY #860-L (ITEM 6 - PART A) MATCH CLOSELY STATIONING SHOWN ON 1958 CONSTRUCTION PLAN (ITEM 4 - PART A). CORNER ACCEPTED AS B-9, BASED ON REMAINING WITNESS NORTH (20.4' TO POST) AND MEASURED DISTANCES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 B-9


- LEFT 1/2" REBAR IN MONUMENT BOX. WITNESSED BY:
- |   |                  |
|---|------------------|
| SET NAIL AND TAG #30090 IN WEST SIDE OF POST              | Az. 0°, 20.04'   |
| SET NAIL AND TAG #30090 IN NORTHEAST SIDE OF 7" POPLAR    | Az. 149° 40.76'  |
| SET NAIL AND TAG #30090 IN NORTHWEST SIDE OF 7" POPLAR    | Az. 203° 39.36'  |
| SET NAIL AND TAG #30090 IN NORTHEAST SIDE OF 20" BASSWOOD | Az. 328° 164.57' |
| SET NAIL AND TAG #30090 IN EAST SIDE OF 20" OAK           | Az. 354° 95.50'  |

Signed by David R. Lohr

Date August 9, 1993.

Surveyor's Michigan License No. 30090

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS  
 PEER APPROVED 8/25/93



PART A CONTINUED

B-9

3. EATON COUNTY ROAD COMMISSION TOPO FIELD NOTES DATED JANUARY 14, 1922 SHOW CORNER FOUND TO BE "IRON PIPE WITH STONE ABOVE. POST IS IN LINE WITH FENCES."

WITNESSED BY:

- OAK CORNER POST NORTH 20.4'
- ELM CORNER POST SOUTH 28.5'
- 12" POPLAR SOUTH 38.8'

4. EATON COUNTY ROAD COMMISSION CONSTRUCTION PLANS FROM 1958 SHOW " APP. SECTION CORNER AT P.I. #13, STA 243 + 67.37'. "T" IRON, WITNESSED BY, STAKE NORTH 25.0', STAKE SOUTH 25.0'. (PLAN SHOWS EXISTING FENCE TO NORTH AT STA. 243 +67)

PLANS ALSO CALL FOR DISTANCE TO WEST TO BE 2645.87' AND DISTANCE TO EAST TO BE 2648.18' (BY STATIONING).

5. CORNER RECORDED BY DOUGLAS K. RICHARDSON, LLS #31603 IN LIBER 3, PAGE 77 ON AUGUST 16, 1988. FOUND 3/4" PIPE ON FENCE LINE TO NORTH. WITNESSED BY:

- NAIL AND TAG IN 8" POPLAR, SOUTH 30° EAST, 30.24' (GONE)
- NAIL AND TAG IN 6" POPLAR, SOUTH 30° WEST, 30.67' (GONE)
- NAIL AND TAG IN 20" OAK, NORTH 05° WEST, 95.50' (FOUND - MEASURED 95.50')
- NAIL AND TAG IN 20" HICKORY, NORTH 40° WEST, 126.82' (GONE)

6. CORNER REFERRED TO BE DOUGLAS RICHARDSON, LS # 31603 ON AUGUST 16, 1988 IN UNRECORDED SURVEY #860-L. SURVEY SHOWS DISTANCE OF 2644.77 FEET WEST TO A-9, AND DISTANCE OF 2648.09 EAST TO C-9.

7. PRIVATE SURVEYOR'S RECORDS REVEAL NO ADDITIONAL DATA.