

FEB 22 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

95 OCT 17 AM 9:27

For corners in WALTON TOWNSHIP
EATON COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1N R 5W I-7 J-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ R _____
- in Section S _____ R _____
- 3. Miscellaneous S _____ R _____
- Property in Section S _____ R _____

LINDA M. TWITCHELL
REGISTER OF DEEDS
EATON COUNTY, MICH.

Copy

LIBER 3 Pg 619

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DAVID R. LOHR, in a field survey on SEPT. 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-7: 1. POST SET IN 1825 BY SILVESTER SIBLEY DEP. SURVEYOR, WITNESSED BY:
 BLUE BEECH 14" S 69° E 30 LINKS (19.80')
 LYNN 14" N 59° W 15 LINKS (9.90')
 SHOWS DISTANCES OF 40.14 CH. EAST AND WEST. NOTE: A DISCREPANCY EXISTS BETWEEN COPIES OF GLO NOTES ON FILE AT THE REG. OF DEEDS AND THE ROAD COMMISSION. R.O.D. NOTES SHOW CORNER SET AT MID-POINT OF 40.14 CHAINS EAST OF I-7, ROAD COMMISSION NOTES SHOWS CORNER SET AT 40.28 CHAINS EAST OF I-7.
 2. NO REFERENCES FOUND IN NOTES OF COUNTY SURVEYOR.
 3. NO REFERENCES FOUND IN PRIVATE SURVEYORS RECORDS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7: SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND REMAINS OF ANCIENT ANCHOR POST SET IN STONES, ON OLD FENCE LINES TO NORTH AND EAST. POST IS 1.5 FT. NORTH X 1.5 FT. WEST OF MODERN ELECTRIC FENCE POST. TRAVERSED ENTIRE SECTION 14 AND MEASURED WEST 2683.19 FT. TO I-7. ACCEPTED LOCATION OF ANCIENT ANCHOR POST AS CORNER, SET 3/4" X 24" STANDARD REMON. BAR/PA345 CAP #30090 IN ITS CENTER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7: SET 3/4" X 24" STANDARD REMON. BAR WITH PA 345 CAP #30090 IN REMAINS OF ANCIENT ANCHOR POST. WITNESSED BY:

SET N/T #30090 W/S OF 24" BEECH	AZ. 04° 31'	44.15'
SET N/T #30090 S/S TW. 8"-16" ASH	AZ. 97° 42'	38.53'
SET N/T #30090 SW/S 14" BEECH	AZ. 148° 21'	28.52'
TRAV. PT. WL2-2-86 1/2" IRON	AZ. 154° 01' 44"	111.98'
SET N/T #30090 W/S 12" ASH	AZ. 340° 14'	13.42'



Signed by David R. Lohr

Date OCT 04 1995

Surveyor's Michigan License No. 30090

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

P.A. 345 EATON COUNTY
PEER APPROVED 9/28/95 ML