

Page 2

K-9: PART A - CONTINUED

3. CORNER REFERRED TO ON EATON COUNTY ROAD COMMISSION BELLEVUE ROAD PLANS DATED MARCH 19, 1923 BY H.A. WILLIAMS

"SECTION CORNER COM. TO SECTION 23, 24, 25 AND 26
 STA 53 + 9.5 (MEAS. FROM THE WEST) - 2 1/2" X 4' STEEL SHAFT,
 TRIPLE MAPLE S 39 1/2° W 44.3'
 MAPLE (36") N 60 °E 39'
 ELM (15") S 3 1/2° E 39.3'

4. CORNER REFERENCED IN SURVEY RECORDED IN LIBER 3 PAGE 676, DATED

JULY 2, 1984 BY ROBERT REED PS #19004.
 "7/8" PIPE" WITNESSED BY:

13" ASH N 37° 48' 55" W, 51.28'
 15" WILLOW N 33° 19' 01" E, 80.82'
 7" ASH S 09° 48' 55" W, 114.08'

5. CORNER REFERENCED IN SURVEY RECORDED IN LIBER 4 PAGE 969.
 DATED SEPTEMBER 15, 1987 BY LARRY BRYAN, PS #25832.
 FOUND 3/4" PIPE C/L BELLEVUE & MATHEWS ROADS. WITNESSED BY:

SET N & T #25832 W SIDE 48" WILLOW, N 35° E, 80.82'
 SET N & T #25832 E SIDE 18" WALNUT, S 10° W, 114.08'
 SET N & T #25832 N SIDE POWER POLE, S 80° E, 100.80'

SURVEY SHOWS DISTANCE NORTH TO K-8 OF 2644.81 FT.

6. CORNER REFERENCED ON LCRC BY LARRY BRYAN, PS #24832 RECORDED IN
 LIBER 3, PAGE 52, DATED OCTOBER 14, 1987.
 FOUND 3/4" PIPE WITNESSED BY:

SET N & T #25832 W SIDE 48" WILLOW, N 35° E, 80.82'
 SET N & T #25832 E SIDE 18" WALNUT, S 10° W, 114.08'
 SET N & T #25832 N SIDE POWER POLE, S 80° E, 100.80'

7. NO OTHER REFERENCES FOUND.